Status of Activities Related to EPICS and Accelerator Control in China

> Presented by Guobao Shen KEKB Control Group

**EPICS** Collaboration

RICOTTI Tokai, 8 Dec 2004

# Outline

- □ Introduction
- EPICS Status in China
  - SSRF LINAC
  - BEPCII
  - HLS
  - CSNS
- References and Special Thanks

# Introduction


- Started in the middle of 1990s
  - IHEP started EPICS research around 1995
  - HLS started from 1996
  - The first EPICS seminar was hold in IHEP at 1997
  - IHEP got the EPICS license at Jan. 1997
  - HLS got the EPICS license at Jan. 1997
  - SSRF got the EPICS license at 1998




## Status in SSRF LINAC -- Introduce

#### SSRF project

- Intermediate energy 3rd generation SR light source
- Suspended for almost 2 years from 2001
- Formal approval by Government at Jan. 2004
- Control System will be based on EPICS
- 100 MeV LINAC
  - Approval in 2002
  - Now under constructing
  - Commissioning started at the beginning of Nov. 2004
  - Will be upgraded to 300MeV for FEL (?)





Dec 2004

## Status in SSRF LINAC -- System Configuration

#### 5 subsystems

- Power Supply, Vacuum, RF, Timing and interlock, Beam Diagnostics (Labview, non-EPICS)
- □ 3 OPIs
  - PC with Linux Redhat 9
- □ 3 IOCs
  - 2 Motorola MVME2302
  - 1 Motorola MVME162
- 12 Controllers
  - 2 A-B SLC 500, 1 A-B PLC 5, 6 A-B 1794 DeviceNet
  - 2 Industrial Pack (IP) Modules, directly VME I/O

## Status in SSRF LINAC -- Record Types


#### □ Total: ~1,500 Records

#### Ai, Ao, Bi, Bo, Mbbi, Mbbo, Subroutine

Subsystem	Equip.	PVs						
		AI	AO	BI	BO	MBBI	MBBO	
Gun	1	8	1	4	1	1	1	
RF	9	41	16	12	5	1	1	
Modulator	1	9	0	10	4	0	0	
P.S.	46	45	45	90	45	0	0	
Vacuum	20	52	16	92	82	8	8	
Other	2		-	16	8		-	
Total	79	157	86	216	1145	10	10	


#### \*\*2 years old, see reference 1

Dec 2004





Dec 2004

## Status in SSRF LINAC -- OPI (1)



## Status in SSRF LINAC -- OPI(2)





### Status in SSRF LINAC -- OPI(4)


PFEIFFER TPG262 CO Pressure Warning Set Low High					Setpoint Status Warry Alarm		Vacuum Device Cont				
CPG1	1.440e-08	Torr	[1.000e	-07 5.000e	-07	1.000e-04	1.100e-04				
	*.	1	1.000e	-07 5.000	-07	1.0000-04	1.1000-04				
	NORMAL DAMAGE STATE	V	a antro Minar	100 edilwa warian.	-					- 2 8	)
CPG2	1.040e-08	R									
					VAR	IAN Mul	lti-Gau	ge CONI	ROL		
CPG3	1050=02	Te						0.0000000			
cr us [	1.960e-08 To Pressure		Warning Set Low High		Alarm Set Low High		Setpoint Status Warning Alarm				
CPG4		Ì.	BAG1	1.318e-09	Torr	1.000e-07	3.0000-07	1.0000-04	1.100e-04		
CPG4	1.420e-08	10				1.000-07			PUMP	POWER SU	PPLY CONTROL
					-	1	IPC01	HV(kV)	IC(uA)	T.14e-09	Online Overrange Roast BKV 4kV
			BAG3	3.148e-09	Torr	1.000e-07	IPC02	5.410	5.5	4.140-10	
						1.000-07	IPC03	5.470	6.2	4.66 e-10	LEVION JEV O
			r				IPC04	6,430	2,6	1.956-10	
			BAG5	1.548e-09	Torr	8.000e-08	IPC05	6.460	3.9	2,78e-10	EXV OH EXV O
			receiter [	March March March	[		IPC06	6,480	12.5	9,40#-10	EKV ON EKV O
		_				8,000e-08	IPC07	6.490	4.9	3.688-10	GRV-OH BRV-OH
						· · · · · ·	IPC08	5,440	3.1	2.33++10	EKV.OH BKV.O
							IPC09	6.440	6.1	4.590-10	ERV.OH EKV.O
							IPC10	6,460	3.4	2.56e-10	SKY OF
							IPC11	6,460	7.1	5.34e-10	ERV OIL ERV OIL
									200	and the second	
							IPC12	5,460	4.7	3.550-10	EKV OH BKV O
							IPC12 IPC13	5,460 6,490	4.7	2.41e-10	ERV OH ERV OF

### Status in SSRF LINAC -- Central Control Room



Dec 2004

## Status in SSRF LINAC -- CRT Monitor



16

## Status in SSRF LINAC -- Rack of IOC, Trigger, Timing and B.M.



Dec 2004

## Status in SSRF LINAC -- Power Supply Room



## Status in SSRF LINAC -- Work Hard



Dec 2004





- Introduction
- □ EPICS Status in China
  - SSRF LINAC
  - BEPCII (Materials are provided by Prof. Jijiu Zhao)
  - HLS
  - CSNS
- References and Special Thanks



- □ BEPCII Control System
  - Based on EPICS
  - R&D has been done in DEC. 2003
  - Development started in Spring of 2004
  - Under construction and in good progress
- System data of BEPCII
  - 1729 devices (930 at BEPC)
  - About 20,000 channels (4,500 at BEPC)

## Status in BEPCII -- Control System Structure






## Status in BEPCII

- -- System Configuration
- 7 subsystems
  - Power Supply, RF, Vacuum, Beam Diagnostic, Injection, LINAC, Interlock
- OPI
  - SUN Solaris BLADE 2000, some Linux PCs
- □ 31 IOCs:
  - 22 MVME5100s for transport lines and storage rings
  - 7 MVME5100s for Timing Systems
  - 2 MVME2431s for LINAC
- Local Controller
  - Fieldbus: CANbus, ControlNet
  - **RS-232**
  - PLC: AB-PLC, S7-PLC(Siemens)

Dec 2004




### Status in BEPCII -- Number of devices and channels

Device	Num.	AI	AO	DI	DO	WF	othe	Sum
Power supply	399	399	399	1596	798		٢	3192
Vacuum	517	957	398	814	994		488	3651
Injection kicker	8	8	16	40	4	4		72
Radio frequency	7	72	35	180	50	4		341
Beam diagnostic	459	864		80	80	6		1030
Injector Linac	325	559	198	228	198	36		1219
Summary	1715	2859	1046	2938	2124	50	488	9505

#### **\*\* 2 years old, See Reference 3**

tatus in BEPCII Present Status
Power Supply prototype has been done in Dec. 2003
Supported Functions: On/off, settings/readings, status monitor
Event timing system
New design finished in May 2004
Software design began in September
now software analysis is under way
Vacuum
prototype has been done
collecting pressure and data of I.P. to IOC with RS-232
Cryogenic control
Communication software between IOC and PLC has been done

#### Status in **BEPCII** -- Present Status (Cont.) RF Klystron system is testing Injection control for Kicker Power Supply Driver and application are developing Linac Use SNL to carry out the ramping Use EDM and TCL/TK to build OPI Have been put into use in Nov. 2003 High level application -- SAD all of source and most of data file from KEKB In Jan. 2003 Built on SUN workstations Main panel transfer from KEKB Good collaboration between KEKB and IHEP




# Status in BEPCII -- OPI (1)

#### Prototype of Power Supply Control



Dec 2004


#### Status in **BEPCII** -- OPI (2) /e-pdi-t/home/sust/cat/s-play/main edi LINAC Power Supply Control **BEPCH Linac Power Supply Control System Quadruple Magnet PS Control** PS Control REF. ON/OFF ALARM SET REF. ON/OFF ALARM SET NAME SAMPLE SETTING NAME SAMPLE SETTING O Magnet SET SET 12.01 11.84 11.84 11.74 11,74 11:88 D Magnet SE1 SET 11.51 11.45 11.45 9.34 9.34 33 F Magnet P Mannet SET SET 12.58 12.53 8.96 12.53 9.02 8.95 Mode ope so a E Magnet SET



31

# Status in BEPCII -- OPI (3)


#### Beam Optics Calculation Application (SAD)



32

# Status in BEPCII -- OPI (4)

#### COD Correction Application (SAD)




Dec 2004

# Status in BEPCII -- MCC and New Console



Dec 2004

# Status in BEPCII -- Chopper on-line testing



35

# Status in BEPCII -- Prototype of PS control



Dec 2004

# Outline

- Introduction
- □ EPICS Status in China
  - SSRF LINAC
  - BEPCII
  - HLS (Materials are provided by Associate Prof. Gongfa Liu)
  - CSNS
- References and Special Thanks


### Status in HLS -- Instruction


#### ] HLS

- 2nd generation dedicated synchrotron light source
- 200MeV electron LINAC and 800 MeV electron storage ring
- New Control System
  - Phase II started from April 1999 formally
  - Prototype system set up at May 1999
  - First subsystem commissioning at June 2000

Last subsystem commissioning at Oct. 2003

#### Status in HLS -- New Control System Structure





### Status in HLS -- System Configuration

- **6** Subsystems
  - Power supply, RF, Vacuum, BPM, Interlock, Water
- □ 21 OPIs
  - 1 Sun Ultra 1, 3 Sun Ultra 10, 1 Sun E250, 2 PC (Linux), 14 PC (Windows)
- □ 17 IOCs」 **□** 
  - IPC (with Flash Disk)
- 107 Local Controllers
  - **56 IPC (with Flash Disk), 12 PLC, Others, 39**

#### Status in HLS -- Detail Lists of Subsystems


		-								
subsystem			ntroller	OPI						
subsystem	IPC	IPC		Other	SUN Ultra	SUN Ultra	SUN	PC/Linux	PC/Windo	
Ring main mag. PS	3	12	J	1 <sup>5</sup> 2	1	130	E2150	2	ŵ\$	
Ring corr. Mag.PS	1	8								
Ring vacuum	1			6						
Ring Flag				1						
Injection system			3							
RF	2	1	2	1						
Water system	1									
RFKO	1			2						
Ring octupole mag. PS	1									
Transport line mag. PS	2	20								
Switch mag. PS	1			1						
Kly. focusing coil PS	1	6								
Analysis Mag. PS		1								
Linac vacuum	1			15						
Linac mag. PS	1	8								
Linac Flag	1			1						
interlock			1							
Linac Modu. pulse PS			6							
01100	17	56	12	39	1	3	1	2	14	
sum	Sum 17 107 21									

Dec 2004

### Status in HLS -- Record Statistics

Subsystems	Record Number
Ring main mag. PS	~400
Ring corr ector mag. PS	~250
Transport line mag. PS	~800
Linac mag. PS	~300
RF	~150
Vacuum	~200
Injection system pulse PS	~50
Flag	~50
Others	~300
sum	~2500

Dec 2004



# Status in HLS

- -- Upgrade process
- May 1999
  - set up a prototype system
- □ June 2000
  - First subsystem commissioning (Storage ring main magnet power supply control system)
- Oct. 2003
  - Last subsystem commissioning (Storage ring Octupole magnet power supply control system)
- □ June 2003
  - upgrade EPICS base R3.13.0.beta12 \_> R3.13.8




- Total 5 persons
- □ 3 persons related to EPICS

Dec 2004

### Status in HLS -- OPI (1)

#### Main Control Panel




Dec 2004

### Status in HLS -- OPI (2)

			KingtanPs2.ad				
_	<b>~</b>			iin P.S. Contro	to all second hours and the		Q:Comm States
Power Supply Control			Beam Current: File: 1	mer Swit Timer Of Timer On Imer Vals			
			P.S. Name P.S. Status amond al Csw Mww Err Ramp		Setting Weight	Rea HEX	dBacks DCCT (A)
			CBEND	0.00	2.02	Oxb	0.01
			201 • • •	0.00	0.31	0x8	0.03
Inactronal/Strentor.adl			202	0.00	0.19	Oxe	0.01
	Linac and Transp	ort line PS Status Moni		0.00	0.45	0x10	0.00
Klystron Focus	Linac PS	Trans KlyEast	Trans Triangle	0.00	9.69	Øxa	0.01
File: 1	File: 1	File: 1	File: 1	0.00	0.60	Øxf	0.01
				0.00	0.45	0x10	-0.01
All Klystron Focus	QAll Linne PS	DAll Trans KlyEast	ChAll Trans Triangle	0.00	0.20	0x77	0.01
PowerError	CtrMain Error	Ctrl Main Error	CtrlMain Error	0.00	0.31	0x4a 0x0	0.03
0.#1 🥯 😶	(2×1) • • •			0.00	0.06	0x0	-1.78
D. 40	G#2 000	1942 😑 😑 👛	13.421 👄 👄 👄	0.00	0.12	0x0	0.01
<u>L12</u> 🗢 🗢	All Parts	D:#3 🕒 😐 🐽	(dit a)		per la		-
Q1#3 🔴 🙂	5h#a] 🔴 🔴 🔵	D#41 0 0 0	<u>[2#3]</u>				
B#4 0	5#4	Q1/5 0	D#4  • •				
	Seal of the last	0/*6	Network 1				
Q#5 😑 😊	Q#5 @ @ O	International Contraction of the	Di#5  👄 👄 🖷				
	(146) <b>O</b> O	0.46	Ch#6   • • •				
	G#7   • • •	(G#9) 🔴 🔴 😐					
		G#10 0 0					
	<u>Garrel</u> 🔴 🔴 😐		<u>[]]#8</u>				
Dec 2004	ŀ	RICOTTI Tokai,	EPICS Collaboration Mee	ting 2004			48

### Status in HLS -- OPI (3)

#### **Ring Vacuum Monitor**



Dec 2004

### Status in HLS -- OPI (4)

Ramping Control	<u>File Edit</u>	⊻jew <u>T</u> ools	Options Others	jalo		
			Latti	ce Layout		
	- 1					
	Energy(Mev)					
	BEND	0.0	203.5034	405.7242	611,2969	051.5402
	01	0.0024	30.3772	60.9962	91.277	122.733
	02	0.0	19,4177	38.9309	58.7176	76,7316
	63	0.0	44.7363	89.6327	134.7819	100.27
	G4	0.0032	60.3145	121.4791	182.0867	242.0721
	65	0.0	60.6569	121.4747	183.0526	242,1078
	G6	8500.0	44.7586	89.6496	134.7975	180.2572
	67	0.0	18.5054	38.2106	58.1888	78.7523
	06	0.0	30.4631	60.9015	91.361	122.7814
	\$X1	1.3471	14.5001	30.4941	49.2057	70.9901
	\$X2	3.325	8.6312	17.2009	25.8495	34.9708
	\$X3	0.0	0.0	2.3684	2.3684	2.3684
	4				-	
			Ramp	ing Contro	bl	
	Step Length(	A): 0.1	_			Start
	Destination(/		5			Stop
		A. 1	-			
Dec 2004			Collaboration N	Monting 2004		50


### Status in HLS -- OPI (5)

#### Ring Orbit Control (SDDS)

Ei in			Bett		
start the sddscontrollaw task Rorizontal was selected. Vertical was selected. start the sddscontrollaw task	940° (* 16082				
Frint deve. Nr   Beakk j					
Punction Selection 😓 PF Feedba	ick 🥪 Hori	contal Feedbak + Vertical Feedba	k		
Inverse Response Matrix File	t /home/ep	ics/apps/data/sr/codCorrect/cq3e	Browse		
Orbit Offeet File:	/home/epics/apps/data/sr/codCorrect/hiss Brow /home/epics/apps/data/sr/codCorrect/hiss Brow				
Correct Test File:					
	addscontro	llaw options			
steps	(300	averages 10	and of		
gain	0.15	interval in averaging 0.	1]		
interval (s)	2.0		4,055		
corrector delta limit (A)	0.5				
■ verbose dry run hol	d present	values 👅 log actuators 👅 log B	tatistic		
Start Correcti	on Run Ir	formation   ABORT Feedback   Loca	1 Steering		
Repet   Reset from file   Mean	ure Repons	e   Set Reference   Launch ADT			
	A CONTRACTOR ALLON	a harden and a second			

Dec 2004

#### Status in HLS -- Central Control Room



Dec 2004

#### Status in HLS -- LINAC Control Room




# Outline

- Introduction
- EPICS Status in China
  - SSRF LINAC
  - BEPCII
  - HLS
  - CSNS (Materials are provided by Associate Prof. Chunhong Wang)
- References and Special Thanks

### Status in CSNS -- Introduce

#### 

- <u>China Spallation Neutron Source</u>
- 100KW, pulsed neutron source
- 25 Hz repetition frequency
- A LINAC with lower energy
- A rapid cycle synchrotron ring with higher energy
- Jointly host by Institute of Physics, Institute of High Energy Physics and CAS
- □ IHEP response for building the facility
- In the process of R&D



#### Status in CSNS -- Control System

- Include power supply control, vacuum control, RF control and machine safety protection
- EPICS based
  - Many people of CSNS have already accepted
- The preliminary design doesn't yet start.
- Power supply control prototype has started

# Outline

- Introduction
- EPICS Status in China
  - SSRF LINAC
  - BEPCII
  - HLS
  - CSNS
- References and Special Thanks

### References

#### 1. Design Reports of SSRF 100 MEV LINAC

- Songqiang Liu, "CN-T33-100MeV LINAC Control System"
- Jitang Li, Lifang Zheng, Songqiang Liu, "CN-T38-LINAC P.S. Subsystem Control"
- Lifang Zheng, "CN-T51-LINAC Modulator Subsystem Control"
- Shouming Hu, "CN-T53 LINAC RF Subsystem Control"
- Shouming Hu, "CN-T55-LINAC Timing Subsystem Control"
- Jianguo Ding, "CN-T57-LINAC Phase Shifter Subsystem Control"
- Jianguo Ding, "CN-T58-LINAC GUN Subsystem Control"
- Haifeng Miao, Lifang Zheng, Jianguo Ding, "CN-T63-LINAC Vacuum Subsystem Control"
- Jianguo Ding, Lifang Zheng, Shouming Hu, Haifeng Miao, Jitang Li, Songqiang Liu, "An EPICS-based LINAC Control System"

## References (Cont.)

- 3. J. Zhao, "Progress of the Controls for BEPCII", EPICS Seminar In IHEP, 20 August, 2002
- 4. Gongfa Liu, "HLS new control system", EPICS Seminar in Hefei, 4 Mar. 2004
- 5. Materials of BEPCII are provided by Prof. Jijiu Zhao
- 6. Materials of CSNS are provided by Associate Prof. Chunhong Wang
- 7. All photos of SSRF 100MeV LINAC are provided by Associate Prof. Jianguo Ding
- 8. All photos of HLS are provided by Associate Prof. Gongfa Liu

# **Special Thanks**

#### SSRF

- Prof. Songqiang Liu
- Associate Prof. Jianguo Ding
- Associate Prof. Lifang Zheng
- Associate Prof. Shouming Hu
- Associate Researcher Haifeng Miao
- □ BEPCII
  - Prof. ZHAO Jijiu
  - Associate Prof. Chunhong Wang
- HLS
  - Prof. Weimin Li
  - Associate Prof. Gongfa Liu

