


Commissioning of the ion beam gantry at the Heidelberg Ion Beam Therapy Center (HIT)

Michael Galonska

on behalf of the
HIT commissioning team



Introduction




Heidelberg Ion Therapy Center:

- **First dedicated particle therapy facility in Europe**
- **3D intensity controlled raster scanning**
- **Worlds first scanning heavy ion gantry**
- **Patient treatment since 2009**
- **R & D in a broad range of disciplines**


Outline

- **HIT accelerator**
- **Gantry**
- **General beam quality / requirements**
- **Gantry beam quality**
- **Outlook**







The HIT facility



- 2 ECR ion sources (p, C, O, He..)
- Compact 7 MeV/u LINAC
- Compact Synchrotron:
Circumference 65 m
KO-extraction
Spill interruptions
Energy variation
- 3 treatment rooms (3D intensity controlled raster scanning)
- Isocentric scanning heavy ion gantry
- Q-A: quality assurance and R & D



T. Haberer et al., NIM A330 (1993)



The Heidelberg Gantry

45° dipoles

scanner magnets

90° dipole


beam

treatment room

GSI
MT Mechatronics




www.klinikum.uni-heidelberg.de



Pencil Beam Library

Pencil Beam Library

ion species	C, p, O, He,...	Steps
energy	50 – 430 MeV / u	255
focus	4 – 13 mm	4 (6)
intensity	$10^7 - 10^{10}$ / spill	10
gantry angle	$0^\circ - 360^\circ$	36




MIRKO: B. J. Franzczak in: Computing in accelerator design and operation, Springer, Berlin, 1984

37 000 combinations / ion type


- Automated standard procedures for setting and determination of beam quality / beam diagnostics
- Ion optical program MIRKO

control system aspects



- Physical input parameters (accelerator model) set to control values (data supply model)
- Settings stored in DB and device controller for data recall (beam request)
- Fast and reliable data handling
- Interpolation algorithm (energy and gantry angle dependence)




Setting Concept







- Full transmission (beta function within limits)
- Basic setting (gantry and gantry injection!) for all angles keeping variation of beam width independent of gantry angle
- Compensating effect of coupling of hor. and vert. phase space under gantry rotation
- Beam size adjustment with last quadrupole doublet







Beam Size Control



- Energy and angle dependent settings of focusing quadrupoles (beam width)
- Energy and angle dependent settings of dipoles/steerer (beam position)
- Spline interpolation over base points







Interpolation



energy step




gantry angle step








- Energy and angle dependent settings of focusing quadrupoles
- Spline interpolation over base points

Approx. 1 % of overall combinations as interpolation points







Beam Size and Position






Beam Size and Position





Beam size and position over full gantry rotation:

- Beam size within accepted rel. deviation of 25 % (orange lines)
- Beam position within ± 2 mm
- Very good stability and reproducibility
- Residual position deviation compensated by scanning system (fast position feedback)
- Suitable for patient treatment




Beam Size and Position









Carbon:

- Beam size within accepted rel. deviation of 25 %
- Beam position within ± 2 mm in isocenter, ≤ 10 % within ± 3 mm




Beam Size and Position



Protons:

- Beam size within accepted rel. deviation of 25 %
- Beam position within ± 2 mm in isocenter




Summary / Outlook

Summary

- **Pencil beam commissioning completed for subsequent preclinical testing (med tech)**
- **Efficient standard routines and tools for semi-automated beam setting and interpolation developed**

Outlook

- **Presently scanning dose delivery under test aiming for clinical use in early 2012**



Summary / Outlook




courtesy of A. v. Knobloch, SAG

Summary

- Pencil beam commissioning completed for subsequent preclinical testing (med tech)
- Efficient standard routines and tools for semi-automated beam setting and interpolation developed

Outlook

- Presently scanning dose delivery under test aiming for clinical use in early 2012



Summary / Outlook



courtesy of A. v. Knobloch, SAG

Summary

- Pencil beam commissioning completed for subsequent preclinical testing (med tech)
- Efficient standard routines and tools for semi-automated beam setting and interpolation developed

Outlook

- Presently scanning dose delivery under test aiming for clinical use in early 2012

Thanks!