



# Commissioning and Initial Operation of FERMI@Elettra FEL

S. Di Mitri, on behalf of the **FERMI Commissioning Team**  
Project Dir.: **M. Svandrlík** (2011–to date), **S. V. Milton** (2007–2010)

# Outline

---

- ▶ **Project Overview and Achievements**
  - ▶ Science Beamlines
  - ▶ Design Goals and Achievements
  - ▶ Status Report & First Coherent Emission
- ▶ **Machine Status**
  - ▶ Layout & Components
  - ▶ Electron Beam Preparation & Seeding
- ▶ **FEL Commissioning**
  - ▶ FEL Experience
  - ▶ Outlook




# FERMI Project Overview & Achievements

## Science, Design and Achievements

# FERMI at the ELETTRA LABORATORY

SINCROTRONE TRIESTE is a nonprofit shareholder company of Italian national interest, established in 1987 to construct and manage synchrotron light sources as international facilities.



**ELETTRA Synchrotron Light Source:**  
up to 2.4 GeV, top-up mode,  
768 proposals from 39 countries in 2010

# FERMI at the ELETTRA LABORATORY

SINCROTRONE TRIESTE is a nonprofit shareholder company of Italian national interest, established in 1987 to construct and manage synchrotron light sources as international facilities.

## FERMI@Elettra FEL:

100 – 4 nm, fully funded

### Sponsors:

Italian Minister of University and Research (MIUR)

Regione Auton. Friuli Venezia Giulia


European Investment Bank (EIB)

European Research Council (ERC)

European Commission (EC)



**ELETTRA Synchrotron Light Source:**  
up to 2.4 GeV, top-up mode,  
768 proposals from 39 countries in 2010



# FERMI at the ELETTRA LABORATORY

SINCROTRONE TRIESTE is a nonprofit shareholder company of Italian national interest, established in 1987 to construct and manage synchrotron light sources as international facilities.

## FERMI@Elettra FEL:

100 – 4 nm, fully funded

Sponsors:

Italian Minister of University and Research (MIUR)


Regione Auton. Friuli Venezia Giulia

European Investment Bank (EIB)

European Research Council (ERC)

European Commission (EC)


Collaborations:



and many others...



**ELETTRA Synchrotron Light Source:**  
up to 2.4 GeV, top-up mode,  
768 proposals from 39 countries in 2010




. Giannini, S. Noe', D. Zangrando

IPAC'11, 09/11,  
San Sebastian, ES

# FERMI at the ELETTRA LABORATORY

SINCROTRONE TRIESTE is a nonprofit shareholder company of Italian national interest, established in 1987 to construct and manage synchrotron light sources as international facilities.



# SCIENCE BEAMLINES

## ▶ Low Density Matter (coord. C. Callegari):

(Partners: F.Stienkemeier (Un.Freiburg), T. Moller (TU Berlin), K. Prince (ST), S. Stranges (Un. Rome-Sapienza), P. Piseri (Un. Milan) et al.)

- ▶ Structure of nano-clusters .....brightness
- ▶ High resolution spectroscopy.....narrow bw,  $\lambda$ -tunability
- ▶ Magnetism in nano-particles.....circular polarization
- ▶ Catalysis in nano-materials.....fs pulse and stability

## ▶ Elastic and Inelastic Scattering (coord. C. Masciovecchio):

(Partners: A. Dicicco et al. (Univ. Camerino), A. Filipponi et al. (Univ. L'Aquila))

- ▶ Transient Grating Spectr. (collective dynamics at the nano-scale) .....transform-limited bandwidth
- ▶ Pump & Probe Spectr. (meta-stable states of matter).....brightness,  $\lambda$ -tunab.

## ▶ Diffraction and Projection Imaging (coord. M. Kiskinova):

(Partners: H.Chapman et al.(CFEL-DESY), J.Hajdu et al.(Uppsala), M.Bogan et al.(SLAC), M.Pivovaroff,A.J.Nelson et al.(LLNL))


- ▶ Single-shot CDI (bio&solid state struct. with diffr.-limited resol.).....brightness
- ▶ Resonant CDI ('element selectivity' and 'magnetic' imag.)..... $\lambda$ -tunab., circ. pol.
- ▶ Time-resolved CDI (transient nano-scale dynamics)..... $\lambda$ -tunab., circ. pol.




# OUR VISION

FERMI is a **single-pass, 50 Hz, externally seeded FEL facility** producing **soft X-rays**:

<input type="checkbox"/> high peak power	0.3 to GW's range
<input type="checkbox"/> short temporal structure	sub-ps to 10 fs time scale
<input type="checkbox"/> tunable wavelength	APPLE II-type undulators
<input type="checkbox"/> variable polarization	horizontal/circular/vertical
peak brilliance	$10^{30} - 10^{31}$ ph/sec/mm <sup>2</sup> /mrad <sup>2</sup> /0.1%bw
flux	$10^{12} - 10^{14}$ ph/pulse
bandwidth	~ Fourier Transform Limit




# DESIGN GOALS & ACHIEVEMENTS




	<b>Parameter</b>	<b>FEL-1</b>	<b>FEL-2</b>	<b>Units</b>
$\gamma$	Output Wavelength (fund.)	100 – 40	40 – 10	nm
$e$	Peak Power	$\sim 1 - 5$	$> 0.3$	GW
	Repetition Rate	10	50	Hz
	Energy	1.2	1.5	GeV
	Peak Current (core)	200 – 800	800	A
	Bunch Length (fhwm)	0.7 – 1.2	0.7	ps
	Slice Norm. Emittance	1.5 – 3.0	1.0	mm mrad
	Slice Energy Spread	0.20	0.15	MeV
				<b>CDR</b>

# DESIGN GOALS & ACHIEVEMENTS



	<b>Parameter</b>	<b>FEL-I</b>	<b>FEL-2</b>	<b>Units</b>
$\gamma$	Output Wavelength (fund.)	100 – 40	40 – 10	nm
$e$	Peak Power	$\sim 1 - 5$	$> 0.3$	GW
	Repetition Rate	10	50	Hz
	Energy	1.2	1.5	GeV
	Peak Current (core)	200 – 800	800	A
	Bunch Length (fhwm)	0.7 – 1.2	0.7	ps
	Slice Norm. Emittance	1.5 – 3.0	1.0	mm mrad
	Slice Energy Spread	0.20	0.15	MeV
				<b>CDR</b>

# DESIGN GOALS & ACHIEVEMENTS



Parameter	FEL-I	FEL-2	Units
Output Wavelength (fund.)	100 – <b>20</b>	40 – 10 (4)	nm
Peak Power	<b>0.5</b> – 5	> 0.3	GW
Repetition Rate	<b>10</b>	50	Hz
Energy	<b>1.2</b>	1.5	GeV
Peak Current (core)	<b>200</b> – 800	800	A
Bunch Length (fwhm)	<b>0.7 – 1.2</b>	0.7	ps
Slice Norm. Emittance	<b>1.5</b> – 3.0	1.0	mm mrad
Slice Energy Spread	0.20	0.15	MeV



\* achieved

# Commissioning Status Report

- ❑ PI Laser, Gun & Injector: 2009 – **2.5 months.**  
(2008, first Gun tests at MAX-lab.)
- ❑ Linac & First Bunch Length Compressor: 2010 – **3.5 months.**
- ❑ Transfer Line to Main Beam Dump: 2010 – **1.5 month.**
- ❑ 1<sup>st</sup> Coherent Emission at 43 nm: 2010 – **1.5 months.** (13 Dec. 2010)  

---

*Coherent X-rays within 9 months after warm-up*



- ❑ X-ray Transport & Diagnostics: 2011 – **2 months.**  

- ❑ FEL Exponential Gain, Polarization & Tunability: 2011 – **1.5 months.**
- ❑ 65 – 32.5 nm to LDM, TIMEX & DIPROI Lines: 2011 – **1.5 months.**  

---


*First users tests 5 months after 1<sup>st</sup> coherent output*

# First Attempt at Seeded Emission: CHG at 43 nm

- The 1<sup>st</sup> seeded FEL coherent output was observed at 43 nm, 13 December 2010.
- 6 radiators tuned in K via calibration tables. e-beam compressed softly, ~100A.
- After spatial and temporal overlap of the seed laser (260nm, 160fs, 100 MW) with the e-beam, we saw the **coherent emission exceeding spontaneous emission** by several orders of magnitude at a diagnostic photodiode, ~40 m far from the undulator exit.



Shot-to-shot signal [a.u.] from atomic photo-ionization of Nitrogen at  $10^{-5}$  mbar.




see G. Penco's talk  
at FEL Conf. 2011

# Machine Status

Installations, e-Beam Gymnastics and Seeding

# CURRENT FERMI LAYOUT




- ▶ RF Photo-cathode Gun and Injector + up to 1.35 GeV Linac
- ▶ 2 Magnetic Bunch Length Compressors + 2 Bunch Length Monitors
- ▶ RF Vertical Deflector for time-resolved measurements
- ▶ 4 optics Diagnostic Stations + 5 Spectrometers
- ▶ 3 Collimation sections
- ▶ Planar and APPLE-II type Undulators + RF BPMs +  $\gamma/e^-$  Screens + Quad-movers
- ▶ Photon Diagnostics Hutch + X-ray Transport + 3 Beamlines

# LINAC

The previously existing 9-structures S-band Linac has been upgraded with:

1. RF photo-cathode Gun (SLAC/BNL/UCLA).....  $\varepsilon_n = 1 \mu\text{m}$  (450pC, 6 ps, 100 MeV)
2. 7 more CERN/LIL structures..... **1.35 GeV** reached
3. SLED optimization and phase-modulation..... **27 MV/m promising 1.5 GeV (FEL-2)**
4. X-band TW structure  
to be installed for linear time-compression




# MAGNETIC COMPRESSOR

Two movable magnetic chicanes for one- or two-stage bunch length compression have been developed *in house* on improved LCLS design..... **compression factor  $\leq 6$  used for FEL**



# MAGNETIC COMPRESSOR

Two movable magnetic chicanes for one- or two-stage bunch length compression have been developed *in house* on improved LCLS design..... **compression factor  $\leq 6$  used for FEL**



# TRANSFER LINE

**Compact (~30 m) FEL-1/FEL-2 Spreader line; e-beam diagnostics and collimation included.** Followed by the undulators (~30 m) and the **Main Beam Dump** line (~40 m).





"Spreader"



Main Beam Dump


# TRANSFER LINE

**Compact (~30 m) FEL-1/FEL-2 Spreader line; e-beam diagnostics and collimation included.** Followed by the undulators (~30 m) and the **Main Beam Dump** line (~40 m).




# UNDULATOR

Variable gap, planar and APPLE-II type undulators. In house design, manufacturing by KYMA (ST spin-off).....**variable polarization &  $\lambda$ -tuning provided to users**



# UNDULATOR

Variable gap, planar and APPLE-II type undulators. In house design, manufacturing by KYMA (ST spin-off).....**variable polarization &  $\lambda$ -tuning provided to users**





# PHOTON TRANSPORT & DIAGNOSTICS

On-line and off-line X-ray diagnostics. Active mirrors. KB mirrors for  $5\mu\text{m} \times 5\mu\text{m}$  focusing on the sample. 3-way switching system for transport to the beamlines.




# PHOTON TRANSPORT & DIAGNOSTICS

On-line and off-line X-ray diagnostics. Active mirrors. KB mirrors for  $5\mu\text{m} \times 5\mu\text{m}$  focusing on the sample. 3-way switching system for transport to the beamlines.



On-line **spectrometer**, also for FEL pulse energy measurement.




**Photodiode** with Al filter + pico-amperometer measures FEL pulse energy.

# OTHER MACHINE SYSTEMS...




# OTHER MACHINE SYSTEMS...



- 
- ▶ **Controls** (news in M. Lonza's, G. Gaio's and L. Pivetta's talk at ICAL-EPCS 2011)
    - ▶ Tango-based
    - ▶ Real-time framework
    - ▶ elegant-based on-line optics control
    - ▶ MATLAB for Mach. Phys. Applications
    - ▶ Scientific Data Management
  - ▶ **Diagnostics** (see R. De Monte's talk and "Elettra" contributions at DIPAC 2011)
    - ▶ Electro-Optical Sampling
    - ▶ Bunch Length Monitor
    - ▶ Bunch Arrival Monitor
    - ▶ 2μm-res. RF Cavity BPMs
    - ▶ Intra-Undulator Screens
  - ▶ **Timing & Synchronization** (see M. Ferianis' talk at FEL Conf. 2011)
    - ▶ All-optical timing system
    - ▶ Synchronization with femtosecond precision
  - ▶ **Machine Protection System** (see L. Froehlich's talk at DIPAC 2011)
    - ▶ Cerenkov fiber beam loss posit. monitor
    - ▶ On-line dosimeter with MOSFETs
    - ▶ Ionization chamber beam loss monitor
  - ▶ **Lasers** (see M. Danailov's talk at FEL Conf. 2011)

# ELECTRON SOURCE

After 2 months operation:  
**QE depletion**




After UV/Ozone cleaning\*  
routinely implemented at  
machine start-up:  
**QE restored.**



\* W. Kern, Handbook of Semiconductor Wafer Cleaning Technology, W. Andrew Publishing/Noyes (1993).


These pictures: the Cu cathode surface is sampled by a 200  $\mu\text{m}$  laser spot and 10  $\mu\text{j}$ .

# ELECTRON BEAM DIAGNOSTICS




- 29 These data collected by: G. Penco, P. Craievich, M. Petronio, A. Lutman, F. Rossi, M. Predonzani, S. Spampinati

# ELECTRON BEAM DIAGNOSTICS



- 30 These data collected by: G. Penco, P. Craievich, M. Petronio, A. Lutman, F. Rossi, M. Predonzani, S. Spampinati

# ELECTRON BEAM DIAGNOSTICS




- 31 These data collected by: G. Penco, P. Craievich, M. Petronio, A. Lutman, F. Rossi, M. Predonzani, S. Spampinati



IPAC'11, 09/11,  
San Sebastian, ES

# SEEDING

**Spatial overlap** across the modulator is carried out with **two YAG screens**. The e-beam is aligned with **μm resolution** RF cavity BPMS. Seed laser movement done with remotely controlled mirrors.




**Time overlap** at the modulator entrance is carried out with an **Al foil** that reflects the laser out of the chamber and makes electrons producing OTR. The two signals are detected with a CCD and a **fast photodiode**. A **delay line** is used for **sub-ps tuning**.





# SEEDING

**Spatial overlap** across the modulator is carried out with **two YAG screens**. The e-beam is aligned with **μm resolution** RF cavity BPMS. Seed laser movement done with remotely controlled mirrors.




**Time overlap** at the modulator entrance is carried out with an **Al foil** that reflects the laser out of the chamber and makes electrons producing OTR. The two signals are detected with a CCD and a **fast photodiode**. A **delay line** is used for **sub-ps tuning**.





# SEEDING

**Spatial overlap** across the modulator is carried out with **two YAG screens**. The e-beam is aligned with **μm resolution** RF cavity BPMS. Seed laser movement done with remotely controlled mirrors.




**Time overlap** at the modulator entrance is carried out with an **Al foil** that reflects the laser out of the chamber and makes electrons producing OTR. The two signals are detected with a CCD and a **fast photodiode**. A **delay line** is used for **sub-ps tuning**.



# SEEDING

**Spatial overlap** across the modulator is carried out with **two YAG screens**. The e-beam is aligned with **μm resolution** RF cavity BPMS. Seed laser movement done with remotely controlled mirrors.















# FEL-1 Experience & Outlook

## HGHG FEL Commissioning Results, Beamlines, Outlook






# e-Beam Seeding Optimization








# e-Beam Seeding Optimization




# e-Beam Seeding Optimization



# e-Beam Seeding Optimization




# FEL DIAGNOSTICS



The emission of 2 consecutive radiators tuned at 52 nm sums coherently for a proper gap of the phase shifter. PS calibration and model are confirmed.

# FEL DIAGNOSTICS




The emission of 2 consecutive radiators tuned at 52 nm sums coherently for a proper gap of the phase shifter. PS calibration and model are confirmed.

$\Delta E/E \sim \rho_{\text{FEL}} \sim 0.1\%$  does not suppress the FEL but affects the lasing mode (here 43 nm).  
Look for the TEM00 mode!


$\Delta \lambda_{\text{seed}}/\lambda_{\text{seed}} = 0.4\%$ , undulators gap tuning around 52 nm  
→ on-line tunable  $\lambda_{\text{FEL}}$

# PHOTON FLUX Measurements





these are indirect measurements, to be confirmed

# PHOTON FLUX Measurements




# FEL GAIN Measurements

The gain depends on current, seeding power and dispersive line ( $R_{56}$ )




250 pC, no yet beam self-interaction (Dec.'10)



see E.Allaria's talk at FEL Conf. 2011


# COHERENCE Measurements

Spectral Bandwidth: **~1.7 FTL**



Due to CCD issue, the bw depends on the expos. time. Seed laser:  $\Delta\lambda/\lambda=0.3\%$ ,  $\sim 150\text{fs}$ ,  $\sim 1.2 \text{ FTL}$ ,


Transverse Coherence: **2-slits experiment**



Preliminary analysis indicates good spatial coherence. Further quantitative analysis ongoing...

# STABILITY


**Central Wavelength Stability:  $\leq 10^{-4}$  (RMS)**  
**Spectral BW Stability:  $\leq 3\%$  (RMS)**



FEL continuously on supplying exp. stations.  
The spectral stability remains at  $\sim 10^{-4}$  level for hours.


After linac improvements, we achieved 10% flux stability with off-crest acceleration.

**Peak Intensity Stability:  $\leq 10\%$  (RMS)**



# EXP. BEAMLINE Commissioning

- ❑ All 3 Beamlines aligned and receiving FEL. Issues remain concerning focusing mirrors.




# EXP. BEAMLINE Commissioning

- All 3 Beamlines aligned and receiving FEL. Issues remain concerning focusing mirrors.


## Low Density Matter Exp. Station

$\lambda_{\text{FEL}}$ -tunability to scan resonant absorption line (He I s-4p transition around 52 nm). The experiment measures the dependence of the fluorescence signal on  $\lambda_{\text{FEL}}$ .



## DiProl Exp. Station

Coh. diffraction test with a periodic array. Beam passes through a 20 μm pin-hole, attenuated with Al filters. 6 diffraction orders demonstrate good FEL coherence. Interference fringes due to a finite dimension of the sample illuminated area are also visible.




# Issues & Lessons Learned

- ▶ X-ray spot size too large on the samples (focusing mirrors to be optimized)
- ▶ BC2, X-band, Laser Heater, FEL-2, 50 Hz oper. ...still require much work
- ▶ Many smaller issues require attention (and time):
  - ▶ Feedback systems
  - ▶ Transverse wake field-induced emittance growth
  - ▶ E-beam optics matching into FEL undulators


---
- ▶ Seeded FEL starts up quickly after linac maintenance; stays on for hours
  - ▶ *No need to use SASE mode for HGHG optimization.*
- ▶ We face a machine still under active development
  - ▶ *Commissioning involves compromise between sub-systems testing, FEL optimization and set-in-operation for users.*
- ▶ Exponential FEL gain with 40% charge increase and minor machine changes
  - ▶ *Linac shows a large acceptance in “beam parameter space”.*

# Towards Shorter Wavelengths



Lines predicted using M.Xie formulae for expected FERMI parameters assuming 40fs pulse length  
Points Ginger and Genesis simulations for S2E files

# Towards Shorter Wavelengths



Lines predicted using M.Xie formulae for expected FERMI parameters assuming 40fs pulse length  
Points Ginger and Genesis simulations for S2E files

# ACKNOWLEDGEMENTS

The **FERMI TEAM** includes dozens of people who designed, installed, tested and commissioned hundred's of machine systems. They made FERMI being just "short of a miracle", transforming raw ground...



# ACKNOWLEDGEMENTS

The **FERMI TEAM** includes dozens of people who designed, installed, tested and commissioned hundred's of machine systems. They made FERMI being just "short of a miracle", transforming raw ground...



# ACKNOWLEDGEMENTS

The **FERMI TEAM** includes dozens of people who designed, installed, tested and commissioned hundred's of machine systems. They made FERMI being just "short of a miracle", transforming raw ground...



Let me specifically mention and thank here all colleagues who participated in the commissioning shifts and, in particular, that bunch of people that in the last 2 years contributed to the success of FERMI working on most of the shifts:

E. Allaria, R. Appio, L. Badano, R. Bartolini, S. Bassanese, A. Borga, K. Casarin, D. Castronovo, D. Cocco, M. Cornacchia, P. Craievich, M. Dal Forno, R. De Monte, G. De Ninno, P. Delgiusto, S. Di Mitri, B. Diviacco, W. Fawley, E. Ferrari, L. Froehlich, R. Fabris, S. Ferry, G. Gaio, F. Gelmetti, L. Giannessi, E. Karantzoulis, M. Lonza, A. Lutman, B. Mahieu, M. Milloch, M. Musardo, L. Pavlovic, G. Penco, M. Petronio, M. Predonzani, E. Quai, F. Rossi, C. Scafuri, C. Serpico, M. Sjostrom, S. Spampinati, C. Spezzani, C. Svetina, M. Trovo', M. Veronese, A. Vascotto, R. Visintini, M. Zangrando, D. Wang.



*Thank you for your attention*

Questions are more than welcome!