



STATUS OF THE ALBA
SYNCHROTRON LIGHT SOURCE:
FROM COMMISSIONING TO
OPERATION

M.Pont, CELLS-ALBA


08.08.2012

OUTLINE

- ❑ The ALBA synchrotron light source
- ❑ Results of Commissioning
- ❑ Operation in 2012
- ❑ Summary and outlook



- In Cerdanyola del Valles, 15 km N of Barcelona (Spain)
- 150 permanent staff
- Operating budget for 2012: 16 MEUR







Main linac parameters:

| Parameters | | Specifications | Working |
|------------------------|---------|----------------|---------|
| E | MeV | 100-130 | 110 |
| $\Delta E/E$ | rms | < 0.50 | 0.16 |
| Norm. $\epsilon_{x,y}$ | mm·mrad | < 30 | < 15 |


- All parameters within specs
- Operation modes: single bunch & multibunch




Few bunches mode
0.25 nC/bunch at linac exit




Multibunch mode
4 nC at linac exit



$\Delta E/E = 0.16\%$ (rms)



ϵ_x (norm.) ≈ 9 mm·mrad




Main BO parameters:

$C = 249.6 \text{ m}$, shares tunnel with SR

$E = 110 \text{ MeV to } 3.0 \text{ GeV}$

$\epsilon_x \approx 10 \text{ nm}\cdot\text{rad}$


Repetition rate: 3.125 Hz



Main parameters of the Storage Ring

| | |
|----------------------------|----------------------|
| Electron beam energy | 3.0 GeV |
| Storage Ring Circumference | 268.8 m |
| Number of cells | 16 |
| Symmetry | 4 |
| Straight section lengths | 4 x 7.8 m (3 ID's) |
| | 12 x 4.3 m (12 ID's) |
| | 8 x 2.3 m (1 ID's) |
| Beam current | 400 mA |
| Emittance | 4.3 nm.rad |
| Hor. Beam sizes | 100 - 300 um |
| Ver. Beam sizes | 7 – 16 um |
| RF frequency | 500 MHz |


Phase I beamlines: 6 x IDs
1 x Bending



- ❑ Spectral range: from UV (80 eV) to hard x-rays (50 keV)
- ❑ High brilliance: 10^{20} at 2 keV

Bending

RF cavities



SR

Booster

9 March 2011 (2nd day)


➤ Recabling Quads:

✓ Sectors 1&2


✓ Quadrant 1

✓ Quadrant 2


✓ Quadrants 3&4




19h35: 1st turn !



On the same day: 20 turns



13 March 2011, 9h38: 1 second stored beam



SR COMMISSIONING


- ✓ Beam based alignment
- ✓ Feed forward table for IDs
- ✓ Looking for hot spots or high pressure
Changes on some absorbers
- ✓ Use of LOCO for online calibration of the machine



SOFB

- Running every 3 s
- With RF frequency included on SOFB

Beam Stability over 24 h



RMS-Values:

$$\sigma_x = 0.5 \mu\text{m}$$

$$\sigma_y = 0.2 \mu\text{m}$$



OPERATION 2012

OPERATION IN 2012

4300 h of operation

3200 h for Beamlines

1100 h for accelerators development

Beamtime Calendar, January 2012-December 2012

BL operation BL BL commissioning
 SR operation SR SR machine studies, developments, improvements
 Stand-by Sy Standby at night
 Start-up St Start up of accelerators with beam
 Warm-up wu warm-up time for magnets & Linac & RF and sub-systems optimisation
 Public holidays and CELLS off

| January | | | February | | | March | | | April | | | May | | | June | | | July | | | August | | | September | | | October | | | November | | | December | | | |
|---------|-----|---------------|----------|-----|--------------|-------|-----|-------|-------|----------|-------|------|-----|-------|------|-----|-------|------|-----|-------|--------|-----|-------|-----------|-----|-------|---------|-----|-------|----------|-----|-------|----------|--|--|--|
| Week | Day | Shift | Week | Day | Shift | Week | Day | Shift | Week | Day | Shift | Week | Day | Shift | Week | Day | Shift | Week | Day | Shift | Week | Day | Shift | Week | Day | Shift | Week | Day | Shift | Week | Day | Shift | | | | |
| Mo | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| Tu | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| We | | | | 1 | BL BL RU | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| Th | | | | 2 | BL BL RU | | | 1 | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| Fr | | | | 3 | BL BL RU | | | 2 | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| Sa | | | | 4 | COO COO COO | | | 3 | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| Su | 1 | OFF OFF OFF | | 5 | COO COO COO | | | 4 | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| Mo | 2 | 1 OFF OFF OFF | | 6 | RU WM WM | | | 5 | 10 | RU WM WM | | | | | | | | | | | | | | | | | | | | | | | | | | |
| Tu | 3 | OFF OFF OFF | | 7 | RU WM WM | | | 6 | 11 | RU WM WM | | | | | | | | | | | | | | | | | | | | | | | | | | |
| We | 4 | OFF OFF OFF | | 8 | RU WM WM | | | 7 | 12 | RU WM WM | | | | | | | | | | | | | | | | | | | | | | | | | | |
| Th | 5 | OFF OFF OFF | | 9 | RU WM WM | | | 8 | 13 | RU WM WM | | | | | | | | | | | | | | | | | | | | | | | | | | |
| Fr | 6 | OFF OFF OFF | | 10 | RU WM WM | | | 9 | 14 | RU WM WM | | | | | | | | | | | | | | | | | | | | | | | | | | |
| Sa | 7 | OFF OFF OFF | | 11 | WM WM WM | | | 10 | 15 | WM WM WM | | | | | | | | | | | | | | | | | | | | | | | | | | |
| Su | 8 | OFF OFF OFF | | 12 | WM WM WM | | | 11 | 16 | WM WM WM | | | | | | | | | | | | | | | | | | | | | | | | | | |
| Mo | 9 | 2 OFF OFF OFF | | 13 | HW St RU | | | 12 | 17 | HW St RU | | | | | | | | | | | | | | | | | | | | | | | | | | |
| Tu | 10 | OFF OFF OFF | | 14 | St St RU | | | 13 | 18 | St St RU | | | | | | | | | | | | | | | | | | | | | | | | | | |
| We | 11 | OFF OFF OFF | | 15 | BL BL RU | | | 14 | 19 | BL BL RU | | | | | | | | | | | | | | | | | | | | | | | | | | |
| Th | 12 | OFF OFF OFF | | 16 | BL BL RU | | | 15 | 20 | BL BL RU | | | | | | | | | | | | | | | | | | | | | | | | | | |
| Fr | 13 | OFF OFF OFF | | 17 | BL BL RU | | | 16 | 21 | BL BL RU | | | | | | | | | | | | | | | | | | | | | | | | | | |
| Sa | 14 | OFF OFF OFF | | 18 | BL BL RU | | | 17 | 22 | BL BL RU | | | | | | | | | | | | | | | | | | | | | | | | | | |
| Su | 15 | OFF OFF OFF | | 19 | BL BL RU | | | 18 | 23 | BL BL RU | | | | | | | | | | | | | | | | | | | | | | | | | | |
| Mo | 16 | 3 wu wu wu | | 20 | 8 HW St RU | | | 19 | 24 | HW St RU | | | | | | | | | | | | | | | | | | | | | | | | | | |
| Tu | 17 | wu wu wu | | 21 | BL BL RU | | | 20 | 25 | BL BL RU | | | | | | | | | | | | | | | | | | | | | | | | | | |
| We | 18 | St St RU | | 22 | BL BL RU | | | 21 | 26 | BL BL RU | | | | | | | | | | | | | | | | | | | | | | | | | | |
| Th | 19 | St St RU | | 23 | BL BL RU | | | 22 | 27 | BL BL RU | | | | | | | | | | | | | | | | | | | | | | | | | | |
| Fr | 20 | St St RU | | 24 | BL BL RU | | | 23 | 28 | BL BL RU | | | | | | | | | | | | | | | | | | | | | | | | | | |
| Sa | 21 | St St RU | | 25 | SR SR RU | | | 24 | 29 | SR SR RU | | | | | | | | | | | | | | | | | | | | | | | | | | |
| Su | 22 | St St RU | | 26 | SR SR RU | | | 25 | 30 | SR SR RU | | | | | | | | | | | | | | | | | | | | | | | | | | |
| Mo | 23 | 4 HW St RU | | 27 | 9 CSN CSN RU | | | 26 | 31 | HW St RU | | | | | | | | | | | | | | | | | | | | | | | | | | |
| Tu | 24 | BL BL RU | | 28 | BL BL RU | | | 27 | 1 | BL BL RU | | | | | | | | | | | | | | | | | | | | | | | | | | |
| We | 25 | BL BL RU | | 29 | BL BL RU | | | 28 | 2 | BL BL RU | | | | | | | | | | | | | | | | | | | | | | | | | | |
| Th | 26 | BL BL RU | | | | | | 29 | 3 | BL BL RU | | | | | | | | | | | | | | | | | | | | | | | | | | |
| Fr | 27 | BL BL RU | | | | | | 30 | 4 | BL BL RU | | | | | | | | | | | | | | | | | | | | | | | | | | |
| Sa | 28 | BL BL RU | | | | | | 31 | 5 | BL BL RU | | | | | | | | | | | | | | | | | | | | | | | | | | |
| Su | 29 | BL BL RU | | | | | | | 6 | BL BL RU | | | | | | | | | | | | | | | | | | | | | | | | | | |
| Mo | 30 | 5 HW St RU | | | | | | | 7 | HW St RU | | | | | | | | | | | | | | | | | | | | | | | | | | |
| Tu | 31 | BL BL RU | | | | | | | 8 | BL BL RU | | | | | | | | | | | | | | | | | | | | | | | | | | |

Updated 01.03.2012

OPERATION IN 2012

- ✓ Running 24/7 during runs
- ✓ Running 3 shifts/day
 - 8 h / shift with 15 min overlap
- ✓ Monday: Accelerators start-up
- ✓ Tuesday 07h00 – Monday 07h00 Beam for users
- ✓ 2 long shut downs,
- ✓ 5 short (1 w) shut downs

SHIFT ISSUES


- ✓ Need 2 people on shift
- ✓ Crew of 5 operators with additional support from the Accelerator Div.
(14 pax)
- ✓ Always 1 operator on the shift
- ✓ Fast rotation cycle. Proposed by the operators
- ✓ M-A-N-(rest)-Normal-M-A-N-(rest)-Normal

OPERATORS EXPERIENCES

- ✓ Operators have been with us since 2009
- ✓ Have gained experience by participating in installation and commissioning
- ✓ Each one is assigned to a technical group (PS, RF, Diagnostics)
- ✓ Encourage to develop small projects:
 - ✓ Looking after beam statistics
 - ✓ Writing procedures
 - ✓ Preparing troubleshooting guides

Statistics Jan-Jun 2012

- ❑ 1760 hours for BLs
- ❑ 93.9 % beam availability (injection not included)



SUMMARY and OUTLOOK

- ✓ Since May 2012 ALBA is open to external users
- ✓ Operate ALBA for 5000 h in 2013
- ✓ Develop training for new operators
- ✓ From commissioning to operation: Challenge to keep motivation

Thanks for your attention

Questions?