

# Nextef

## Status of high gradient experiment



May 13-15, 2008

2<sup>nd</sup> Collaboration meeting on X-band Accelerator  
Structure Design and Test Program

T. Higo, KEK


# Nextef progress

Establishing power generation and transport in 2007




# Nextef inside shield room

most basic components are now in line.




# Nextef planning



# What are needed for Nextef




- **Enough power**, 55MW, 300ns at accelerator structure, CLIC\_VG1, for 100MV/m
- **Square RF pulse** with variable width
- Operation and **each RF pulse analysis** at 50Hz
- **Stable operation** with BRD < 1BD/hr at most
- Proper control program based on the well-defined **processing protocol**
- **Identification of breakdowns**, distinguishing either at structure or outside

# Nextef Nominal RF power line



# Nextef operation without structure

## RF shape at 50MW, 300ns, 50Hz



Shape rise and fall and flat top


Refl. From load

$$\begin{aligned}
 &2\text{mV} / 89\text{mV} \\
 &= \pm 0.4\text{mW} / 11\text{mW} \\
 &= \pm 4\%
 \end{aligned}$$

Base line jitter or actual?

# Nextef recent typical operation

Blue ~ ACC-IN[MW], Pink = Load Vacuum, Green = Combiner vacuum



Stable operation  
at 50MW level

Load vacuum jump  
with reflection  
from load


Rarely but sometimes vacuum  
jump near **combiner 3dB**, with  
big reflection to klystrons




# Readiness of components

- Nextef: Refer to Matsumoto's talk
- **Klystrons** are tested at **60MW for 300nsec** pulse, which makes the combined power of 120MW.
- **3dB hybrid or WR90 waveguide components** are sometimes arcing at 50MW level now. This needs to be conditioned out or identified to distinguish from the events due to accelerator structure.
- **Loads** are subject to damage due to high pulse energy operation. Proper loads are to be used for the loads downstream of accelerator structure.

# Nextef: Nominal observables along waveguide




# Beam-line setup



Nextef Beam line and waveguide configuration


# Nextef: observables along beam axis



# Preparation status of sensors

- **RF pulse: crystals**
  - Combined, ACC-input are being monitored as feed RF power.
  - F, Rs, Ra and T will be detected with crystals. Each pulse will be analyzed with 7000 series Tektro oscillo. Oscilloscope data taking is under development at KT-1.
- **VAC : cold cathord gauges**
  - CCG monitors are working at various places of WR90 and two points of beam line
- **Dark currents: Faraday cups, analyzer magnet and profile monitors**
  - DC current measurement wit FC is our typical.
  - Transient response of FC is yet to be confirmed.
  - AM should work without problem.
  - The response of profile monitor is not checked after many years idling.
- **Acoustic sensors**
  - Sensors are those from SLAC and used at XTF.
  - VME modules are under preparation for operation.
- **Photomultiplier and scintillator**
  - A few lead-shielded sets are prepared.
- **Q-mass**
  - Operation should be checked.

# Various detection tools are to be integrated into Nextef control system



# Nextef to be done for breakdown detection system

- **Tektro 7104 pulse-to-pulse analysis**
  - Take experience at KT-1
  - Establish the threshold and other parameters
- **RF pulse at all points**
  - Identify the breakdown position in Nextef system
  - Digital data taking and analysis as needed.
- **VME modules**
  - Restart operation program similar to XTF
  - Use as positioning of arc in the system or in the structure.
- **FC, AM, PM, PMT, Q-mass operations**
  - Basic performance should be confirmed. With actual signal or with other source?
- **Red-marked items should be from the beginning of CLIC\_VG1 test.**

# Conclusion

- Nextef power rating is now  $\sim 50\text{MW}$ , 300ns, 50Hz level with less than 1BD/hr.
- We need to establish the detection system in May with KX03.
  - In breakdown detection and analysis at the input power level of 50MW or more.
- We want to start CLIC\_VG1 before summer shutdown of KEKB.
  - Some incompleteness of the system should be tolerated, as long as essential features, such as power evaluation, processing protocol and identification of breakdown, are confirmed.
- We try to operate the Nextef as effectively as possible within the KEK regulation.
  - Hopefully run during shutdown but we admit it not easily be realized.