Present Status and Future Upgrade of KEKB Injector Linac

Kazuro Furukawa, for e-/e+ Linac Group

Present Status Upgrade in the Near Future R&D towards SuperKEKB


Electron/Positron Injector Linac

Machine Features

 600m Linac with 59 S-band rf Stations, most of them Equipped with SLED to provide 20MeV/m
 Dual Sub-Harmonic Bunchers to achieve 10ps for 10nC, and Energy Compression System for Positron

Beam Characteristics

8GeV 1.2nC Electron and 3.5GeV 0.6nC x2 Positron for KEKB
2.5GeV 0.2nC for PF, 3.0GeV 0.2nC for PF-AR



Linac in KEKB Commissioning

Challenging Projects since 1998

- Commissioning (1998~)
- Overcoming rf Breakdowns

at the Bunching section and Positron Capturing section (1999~2000)

Positron Injection with Dual Bunches in a Pulse (2001~2002)

 Reduction of Failure Rate with Careful Management of the Equipment and Beam Parameters, especially at rf Trip Rate (2002)
 C-band R&D for the Future SuperKEKB (2003~)


Continuous Injection of both Positron and Electron Beams (2004)

Recent Operation

- About 7000 hours/year
- ♦ Machine-trouble time (when some part of the machine is broken): 2~3%
- ♦ Beam-loss time (when beam could not be delivered): ~0.5%
- Routine management

of rf Power, rf Phasing, Optics Matching, Energy Spread Optimization

Increase of the Injection Efficiency



Present Status

Continuous Injection Mode

Reliability of the Operation


Frequent Switch was not Considered in the Design

Xacuum Bellows, Mechanical Phase Shifters, etc.

Improvement in each Hardware Component,

as well as Operation Software

No Reliability Degradation is Observed




Positron Generation with Crystalline Tungsten

(Collaboration between KEK, Tokyo Metro. Univ., Hiroshima Univ., Tomsk Polytech., LAL-Orsay)

High Intensity Positron is Always a Challenge in Electron-Positron Colliders

Positron Production Enhancement by Channeling Radiation in Single Crystal Target was Proposed by R. Chehab et. al (1989)

The Effect was Confirmed Experimentally in Japan (INS/Tokyo, KEK) and at CERN




Experiment at KEK


Positron Production Enhancement Measurement

Target Thickness Dependence (2.2, 5.3, 9mm for Tungsten Crystal, 2 ~ 28mm for Amorphous)
Out-going Positron Energy Dependence (5 ~ 20MeV)
Incident Electron Energy Dependence (3 ~ 8GeV)
Single Target or Hybrid Target
Target other than Tungsten,

Crystals used for Calorimeters, Silicon, Diamond




Experimental Setup



Crystalline Positron Target





Crystalline Positron Target

K.Furukawa, Feb.24.2005. 9

Results and Considerations

• With Tungsten Single Crystal, the Absolute Positron Yields were Enhanced by ~26% at E_{e+} =20MeV, and by ~15% (average) in the range of E_{e+} = 5~20MeV compared with the Maximum Yield in the Amorphous Tungsten.

Diamond Hybrid Target has been Suggested to Produce 3-Times more Photons (V.N.Baier et al.), but We need >15mm Thick Diamond while We could test only 5mm. And the Radiation Damage is Unknown.

 Another Experiment is Planned just before Summer Shutdown to Refine the Results, and The Optimized Crystalline Tungsten is Planned to Replace the Present Positron Target. The Design of the Target is Under way.

Upgrade Towards Simultaneous Injection

(Collaboration Working Group between PF, KEKB, Linac and Others)

Requirements

One Linac is used for 4 Storage Rings (Time Sharing)

Switching between KEKB and other Modes takes ~3 minutes because ECS Magnets have to be standardized.

Machine Studies in PF and/or PF-AR Interrupt the KEKB Continuous Injection.

PF Needs Top-up (Continuous) Injection in the Future for Advanced Measurement.


 HER
 1.171 [A]
 1283 [bunches]
 Physics Run

 1.800 [A]
 1284 [bunches]
 Physics Run

 1.915 (now)
 1284 [bunches]
 Physics Run


Possible Solution


 Simultaneous Injection Scheme is Strongly Suggested.
 Beam Switches pulse-by-pulse could be Employed.
 Needs Pulse Bend. Magnet to Kick PF Beam





Fast Beam Switches

- Fast Change of the Magnetic Field is Difficult
 - Common Magnetic Field (Quad and Steering Magnets) should be Used.
 - Energy Adjustment can be Achieved with Low-level rf Controls.
 - ¤With Additional Circuits and Controls.
 - The Beam is Accelerated up to ~5.3GeV then further Accelerated to 8GeV for KEKB, or Decelerated to 2.5GeV for PF.










• Energy = 8 GeV (SC61H) • $\gamma \varepsilon_x = 2.5 \times 10^{-4} \text{ m}$ • $\gamma \varepsilon_y = 4 \times 10^{-5} \text{ m}$

Upgrade Overview


Upgrade would be Carried in 3 Phases
 Phase-I: Construction of New PF-BT Line Summer 2005

- Phase-II: Simultaneous Injection between KEKB e- and PF e-
- Phase-III: Simultaneous Injection including KEKB e+ (,PF-AR)
- It was decided to be Carried out as Soon as Possible.



PF Beam Transport Optics Design

- The New PF-BT Optics Design is Fixed
- Spare Parts are Collected based on the Design, if Exists
- Other Components are being Designed or being Fabricated
- Phase-I Components (except Pulse Bend) will be Installed at this Summer



Simultaneous Injection

C-band R&D towards SuperKEKB

Higher Luminosity in SuperKEKB

- (1) Squeezing Beta at Interaction Region
- (2) Increase of Beam Currents
- (3) Crab Cavities

(4) Exchange of Energies of Electron/Positron to Cure e-Cloud Issuesetc.

For Linac (4) is the Major Challenge as well as (2)

Higher Gradient Acceleration with C-band Structure is Considered to Achieve 8GeV Positron

~24 rf Stations will be Converted

From: Single S-band rf Station + 2m x 4 Acc Structure = ~160MeV

To: Dual C-band rf Station + 1m x 16 Acc Structure = ~320MeV


==> 8GeV Positron can be Provided

Dumping Ring to Meet the IR Design will also be Employed

Advances in C-band R&D

Apr.2002-Aug.2003.

- Design and Installation of
 - **¤**First rf Station
 - - Basically Scale down of S-band One




First Accelerated Beam (Oct.2003) ¤~38MV/m at 43MW

- Sep.2003-Aug.2004.
 - Design and Installation of
 - First LIPS type rf Compressor (SLED)
 - TE038 mode

Linac C-band Test Module #4-4A

Further Improve for Real Operation



 Accelerated Beam with rf Pulse-Compressor
 ~42MV/m at ~56MW (12MW from Kly.)

C-band Components

- Klystron & Pulse Modulator
- Compact (1/3 size), Cooling and IGBT breakdown Issues Solved
 f Window (2)
 - Mix (TE11+TM11) mode Traveling Wave, 300MW Transmission
- 🔶 rf Pulse Compressor 🙂
 - ✤TE038 mode (instead of TE015), Q₀=132,000, 200MW Achieved in Test
- Accelerating Structure
 - Based on half-scale of S-band Structure
 - 2/3p Traveling-wave, Quasi-constant-gradient, Electroplating
 - Because of such Simple Design, a few Trips / hour Observed Expected to be Solved in the Next Summer
- •rf Low-level and booster Klystron
 - May need Modification in Real Operation


Improvements in Coming Summer

Four Accelerating Structures are under Fabrication
 Designed in KEK, and Fabricated in KEK or MHI

Several Features are Applied especially at Coupler

Standard or Non-standard (Full-length) Coupler Cell

- Thick and Smooth Shape Coupler Iris
- Coupler Axis offset for Field Correction
- Electro-polishing at Coupler
- Constant Impedance



C-band R&D

Summary

 Operational Improvements and Future Projects are Carried with Balancing between them

Continuous Injection Surely Improved KEKB Luminosity

 Simultaneous Injection Project will Help both KEKB and PF Advanced Operation, and also Other Rings in Future

Oriented Crystalline Positron Target may Enhance Positron
 Production

C-band R&D for Future SuperKEKB Advances Steadily but relatively Rapidly, and the Results seem to be Promising