

Experiment Liaison Duties

The art of effective experiment preparation
and setup

Michael Aiken

Our Machine

- CEBAF
 - 6 GeV
 - $\sim 100\mu\text{A}$
- Experimental Halls
 - 2 Electron
 - 1 Photon
- Experiment types/classes
 - Class 1 & 2

The Operations Group

- Operational Hours
 - 24/7
- Duration of Runs
 - Typically 3-6 months
 - Downtimes of 1-3 months
- Shift Rotation
 - 6 Crews
 - 8 Hour shifts

The Operations Group

- Staff Structure
 - Group Leader
 - Crew Chiefs / Supervisors
 - Operators
- Typically Shift Staff
 - 1 Crew Chief
 - 2+ Operators

Experiment Setup Complexity

- Beamline Components
 - Chicanes
 - High Magnetic Fields
 - Multiple Dumps
- Required Readbacks
 - Magnet Currents
 - Insertable Devices
- Liaison needed
 - Crew Chief or Operator for each Hall

Collecting Information

- Meetings
 - Weekly Meetings
 - Collaboration Meetings
 - Installation Meetings
- Feedback provided
 - Extra Viewers
 - Extra Correctors

Relaying Information

- Setup Procedure
- Expert Talks



Hall C Beam Delivery Procedure

Document Number: MCC-PR-06-001

Revision Number: Rev. 33; September 16, 2009

Technical Custodian: Mike Aiken

Estimated Time to Perform: Not Applicable

Procedure Overview

This procedure describes the protocol for establishing and maintaining beam delivery to Hall C.

The procedure is divided into sections as follows:

- Section 1.0 [Establishing Initial Orbit to the Hall C HKS Experiment After an Energy Change on page 2](#)
- Section 2.0 [Maintaining Beam Delivery to the Hall C HKS Experiment on page 7](#)


Prerequisites

1. The accelerator has been optimized to meet the specifications in Table 1, below.

Table 1: Accelerator Performance Specifications

Parameter	Specification
Injector	Ready for operations per clear alarm handler and concurrence of injector on-call.
Linac phasing	All RF phases optimized.
Accelerator orbit	Clean transport with all relevant locks On.
Path Length	< 1 degree compared to baseline.
Dispersion	< 1 mm error in non-dispersive locations.
Courant Snyder Invariant	< factor 2 growth compared to Arc1.
Accelerator Aperture	> 1.5V on all 30 Hz correctors > 6V for 30 Hz RF (shown for 4045 MeV; scale for other energies)

2. The Hall C alarm handler is running and the masking configuration is appropriate for beam delivery.
3. The default FSD masks are loaded for Hall C beam delivery.




Knowing the Beamline

- Beam line Drawings
- Tours

BSY 1st Section

EXPERIMENTAL HALL A BEAMLINE



Webpage

- Webpage

http://www.jlab.org/accel/ops/ops_liaison/Hall_C/qweak.html